

**Price Schedule for Goods Offered from Within the Philippines**  
**[shall be submitted with the Bid if bidder is offering goods from within the Philippines]**  
**FOR THE PROCUREMENT OF 750KVA GENERATOR SET WITH A POWER HOUSE**

NAME OF BIDDER \_\_\_\_\_

Project ID No. \_\_\_\_\_

Page \_\_\_ of \_\_\_

1	2	3	4	5	6	7	8	9	10	
Item No.	UNIT of Measure	Brief Description	QTY	ABC/UNIT	Unit price EXW per item	Transportation and all other costs incidental to delivery, per item	Sales and other taxes payable if Contract is awarded, per item	Cost of Incidental Services, if applicable, per item	Total Price, per unit (col 5+6+7+8)	Total Price delivered Final Destination (col 9) x (col 4) Total Price delivered Final Destination (col 9) x (col 4)
1	unit	<p>Supply, Delivery, Installation, Testing and Commissioning of One Unit 750 KVA Standby Generator Set C/W Accessories, Distribution Panel, Transfer Switch, Wirings, and Raceways Including Power House (12m x 8m)</p> <p>GENERATOR SPECIFICATIONS:                      Silent type Standby Diesel Generator Set                      750KVA 3 Phase 230V, 60Hz, 1800rpm, 0.8pf w/ 12 hours base fuel tank                      Dimension (mm) (L x W x H): 4300 x 1900 x 2300                      Weight: 6500kg                      Engine specifications:                      Cycle: 4 stroke                      Aspiration: Turbocharged &amp; air to air intercooled; direct injection                      Starting method: 24V Electric motor starters                      Speed governor: Electronic                      Cooling way: Water-cooled system                      Fuel consumption @100% load Prime load: 161L/h                      Enclosure: IP21                      Control panel: digital                      Complete with accessories</p> <p>DISTRIBUTION PANEL SPECIFICATIONS:                      Distribution Panel 1 (1 set)                      Compartment 1:                      Main Circuit Breaker: 1 x 1000AT/ 1000AF, 3P, 240V 60Hz, 65KAIC MCCB                      Compartment 2:                      Branch Circuit Breakers: 2 x 500AT/600AF 3P, 240V 60Hz, 65KAIC MCCB + 4 space for 600AF, 3P 240V MCCB                      Compartment 3:                      1 x 250AT/250AF 2P, 240V 60Hz 42KAIC MCCB + 1 x 200AT/250AF 2P, 240V 60Hz 42KAIC MCCB + 1 x 175AT/250AF 2P, 240V 60Hz 42KAIC MCCB + 1 x 100AT/250AF 2P, 240V 60Hz 42KAIC MCCB + 1 x 70AT/250AF 2P, 240V 60Hz 42KAIC MCCB + 1 space for 250AF 2P, 240V MCCB</p> <p>Complete with accessories, mechanical lugs, grounding bus and digital display metering for Voltage/phase, Current/phase, Frequency/phase in NEMA 3R type enclosure floor mounted</p>	1	11,800,000.00						
		<b>SUPPLY, DELIVERY AND INSTALLATION OF UNDERGROUND FEEDER CONDUCTORS, RACEWAYS AND TRANSFER SWITCHES INCLUDING TRENCHES AND HANDLE ENCLOSURES</b>								
		<b>CONDUITS, BOXES, FITTINGS AND ACCESSORIES</b>								
1	piece	uPVC Pipe thickwall, 32mmØ x 3m	2	132.00						
2	piece	uPVC Pipe thickwall, 40mmØ x 3m	8	267.00						
3	piece	uPVC Pipe thickwall, 50mmØ x 3m	10	367.00						
4	piece	uPVC Pipe thickwall, 65mmØ x 3m	1544	471.00						
5	piece	uPVC Elbow 32mmØ 90°	2	75.00						
6	piece	uPVC Elbow 40mmØ 90°	4	100.00						
7	piece	uPVC Elbow 50mmØ 90°	6	100.00						

Item No.	UNIT of Measure	Brief Description	QTY	ABC/UNIT	Unit price EXW per item	Transportation and all other costs incidental to delivery, per item	Sales and other taxes payable if Contract is awarded, per item	Cost of Incidental Services, if applicable, per item	Total Price, per unit (col 5+6+7+8)	Total Price delivered Final Destination (col 9) x (col 4)	Total Price delivered Final Destination (col 9) x (col 4)
8	piece	uPVC Elbow 65mmØ 45°	48	133.00							
9	piece	uPVC Elbow 65mmØ 90°	91	133.00							
10	set	RSC Clamp 32mmØ w/ screw	6	24.00							
11	set	Conduit Clamp; 40 mm dia, Metal, U-Bolt, Stainless	24	30.00							
12	set	Conduit Clamp; 50 mm dia, Metal, U-Bolt, Stainless	30	38.00							
13	set	Conduit Clamp; 65 mm dia, Metal, U-Bolt, Stainless	20	50.00							
14	length	Z - bar; 1/8"thk. x 1" x 20'	2	1,100.00							
15	set	Expansion shield 1/4"Ø x 2"	30	14.50							
16	piece	Pull Box w/ cover; NEMA 3R 300mm x300mm x150mm Deep	2	700.00							
17	piece	Pull Box w/ cover; NEMA 3R 400mm x400mm x150mm Deep	3	1,000.00							
18	piece	Pull Box w/ cover; NEMA 3R 600mm x600mm x250mm Deep	4	1,200.00							
19	can	PVC Solvent Cement; 400 cc	20	200.00							
20	roll	Caution Buried Electric Line Below Warning Tape 3" x 1000'	3	2,500.00							
<b>ELECTRICAL WIRINGS, CONNECTORS AND ACCESSORIES</b>											
21	meter	Electric wire THWN-2 5.5mm² Cu. Str., 600V	200	37.00							
22	meter	Electric wire THWN-2 8.0mm² Cu. Str., 600V	650	71.00							
23	meter	Electric wire THWN-2 14mm² Cu. Str., 600V	1090	95.00							
24	meter	Electric wire THWN-2 22mm² Cu. Str., 600V	470	197.50							
25	meter	Electric wire THWN-2 30mm² Cu. Str., 600V	1500	227.00							
26	meter	Electric wire THWN-2 38mm² Cu. Str., 600V	520	371.00							
27	meter	Electric wire THWN-2 60mm² Cu. Str., 600V	340	499.00							
28	meter	Electric wire THWN-2 80mm² Cu. Str., 600V	30	594.00							
29	meter	Electric wire THWN-2 100mm² Cu. Str., 600V	310	747.00							
30	meter	Electric wire THWN-2 125mm² Cu. Str., 600V	30	1,115.00							
31	meter	Electric wire THWN-2 175mm² Cu. Stranded, 600V	8046	1,335.00							
32	piece	Split bolt connector, copper, 60mm² Stranded	1	500.00							
33	piece	Split bolt connector, copper, 175mm² Stranded	8	1,300.00							
34	piece	Circuit breaker mechanical lug kit, for 2 x 175mm² Stranded conductors 400A rated current	6	750.00							
35	piece	Circuit breaker mechanical lug kit, for 2 x 175mm² Stranded conductors 500A rated current	6	750.00							
36	roll	PVC Tape/19 mm dia x 18 mm	83	30.00							
37	roll	Rubber Tape/ Friction Tape/19 mm dia x 227 g	75	37.00							
<b>TRANSFER SWITCHES</b>											
38	set	Manual Transfer Switch (MTS) 100AT, 2P, 240V, 60Hz NEMA 3R Enclosure c/w accessories	3	14,300.00							
39	set	Manual Transfer Switch (MTS) 150AT, 2P, 240V, 60Hz NEMA 3R Enclosure c/w accessories	2	19,500.00							
<b>HANDHOLES AND TRENCHES</b>											
40	bags	Portland Cement	168	306.00							
41	cu.m.	Fine Aggregate	32	850.00							
42	cu.m.	Crushed Gravel, 3/4"	18	975.00							
43	piece	10mmØ x 7.5 RSB	27	236.00							
44	piece	10mmØ x 7.5 RSB	53	190.00							
45	kgs	# 16 G.I. Tie Wire	3	75.00							
46	bd.ft	Coco Form Lumber	96	40.00							
47	piece	1/2" thk. 4' x 8' Marine Plywood	32	610.00							
48	kgs	Assorted Common Nail	3	75.00							
49	lot	INSTALLATION COST	1	5,200,000.00							
<b>NOTE: LOT EVALUATION</b>											

Name: \_\_\_\_\_  
Legal Capacity: \_\_\_\_\_  
Signature: \_\_\_\_\_  
Duly authorized to sign the Bid for and behalf of: \_\_\_\_\_

**Statement of all Ongoing Government & Private Contracts, including contracts awarded but not yet started,  
if any, whether similar or not similar in nature and complexity to the contract to be bid**  
PROCUREMENT OF 750KVA GENERATOR SET WITH A POWER HOUSE

Business Name: \_\_\_\_\_  
Business Address: \_\_\_\_\_

Name of Contract/ Project Cost	a. Owner's Name b. Address c. Telephone Nos.	Nature of Work	Bidder's Role		a. Date Awarded b. Date Started c. Date of Completion	% of Accomplishment		Value of Outstanding Works / Undelivered Portion
			Description	%		Planned	Actual	

- Note: This statement shall be supported with:
1. Notice of Award and/or Contract
  2. Notice to Proceed issued by the owner
  3. Certificate of Accomplishments signed by the owner or authorized representative

Submitted by: \_\_\_\_\_  
(Printed Name & Signature)

Designation: \_\_\_\_\_  
Date: \_\_\_\_\_

**Statement of Single Largest Completed Contract (SLCC) similar to the contract to be bid,  
except under conditions provided for in Sections 23.4.1.3 and 23.4.2.4 of the 2016 revised IRR of RA 9184,  
within the relevant period as provided in the Bidding Documents  
PROCUREMENT OF 750KVA GENERATOR SET WITH A POWER HOUSE**

Business Name: \_\_\_\_\_

Business Address: \_\_\_\_\_

Name of Contract	1. Owner's Name 2. Address 3. Telephone Nos.	Nature of Work	Bidder's Role		a. Amount at Award b. Amount at Completion c. Duration	a. Date Awarded b. Contract Effectivity c. Date Completed
			Description	%		

Note: This statement shall be supported with:  
 1. Contract/Purchase Order  
 2. Certificate of Completion  
 3. Certificate of Acceptance

Submitted by: \_\_\_\_\_  
 (Printed Name & Signature)

Designation: \_\_\_\_\_  
 Date: \_\_\_\_\_