

Price Schedule for Goods Offered from Within the Philippines
[shall be submitted with the Bid if bidder is offering goods from within the Philippines]

PURCHASE OF MACHINERY AND EQUIPMENT (SUPPLY, DELIVERY, INSTALLATION, TESTING & COMMISSIONING OF 750KVA STANDBY GENSET, TRANSFER SWITCHES, DISTRIBUTION PANELS INCLUDING GENERATOR HOUSE AND UNDERGROUND CABLING)

Name of Bidder: _____

Project ID No.: _____ Page ___ of ___

1	2	3	4	5	6	7	8	9	10	
Item	Unit of Measure	Brief Description	QTY	ABC/Unit	Unit price EXW per item	Transportation and all other costs incidental to delivery, per item	Sales and other taxes payable if Contract is awarded, per item	Cost of Incidental Services, if applicable, per item	Total Price, per unit (col 5+6+7+8)	Total Price delivered Final Destination (col 9) x (col 4)
		Supply, Delivery, Installation, Testing & Commissioning of 750KVA Standby Genset with Accessories, Distribution Panels, Transfer Switch, Wirings and Raceways, Including Generator House								
1	lot	<p>GENERATOR SPECIFICATIONS:</p> <p>Silent type Standby Diesel Generator Set 750KVA 3 Phase 230V, 60Hz, 1800rpm, 0.8pf w/ 12 hours base fuel tank</p> <p>Dimension (mm) (L x W x H): 4300 x 1900 x 2300</p> <p>Weight: 6500kg</p> <p>Engine specifications:</p> <p>Cycle: 4 stroke</p> <p>Aspiration: Turbocharged & air to air intercooled; direct injection</p> <p>Starting method: 24V Electric motor starters</p> <p>Speed governor: Electronic</p> <p>Cooling way: Water-cooled system</p> <p>Fuel consumption @100% load</p> <p>Prime load: 161L/h</p> <p>Enclosure: IP21</p> <p>Control panel: digital</p> <p>Complete with accessories</p>	1	8,197,999.53						
2	lot	<p>DISTRIBUTION PANEL SPECIFICATIONS:</p> <p><i>Distribution Panel 1 (1 set)</i></p> <p>Compartment 1: Main Circuit Breaker: 1 x 1000AT/1000AF, 3P, 240V 60Hz, 65KAIC MCCB</p> <p>Compartment 2: Branch Circuit Breakers: 2 x 500AT/600AF 3P, 240V 60Hz, 65KAIC MCCB + 4 space for 600AF, 3P 240V MCCB</p> <p>Compartment 3: 1 x 250AT/250AF 2P, 240V 60Hz 42KAIC MCCB + 1 x 200AT/250AF 2P, 240V 60Hz 42KAIC MCCB + 1 x 175AT/250AF 2P, 240V 60Hz 42KAIC MCCB + 1 x 100AT/250AF 2P, 240V 60Hz 42KAIC MCCB + 1 x 70AT/250AF, 2P, 240V 60Hz 42KAIC MCCB + 1 space for 250AF 2P, 240V MCCB</p>	1	410,250.00						

1	2	3	4	5	6	7	8	9	10	
Item	Unit of Measure	Brief Description	QTY	ABC/Unit	Unit price EXW per item	Transportation and all other costs incidental to delivery, per item	Sales and other taxes payable if Contract is awarded, per item	Cost of Incidental Services, if applicable, per item	Total Price, per unit (col 5+6+7+8)	Total Price delivered Final Destination (col 9) x (col 4)
		Complete with accessories, mechanical lugs, grounding bus and digital display metering for Voltage/phase, Current/phase, Frequency/phase in NEMA 3R type enclosure floor mounted								
3	lot	Distribution Panel 2 (1 set) Compartment 1: Main Circuit Breaker: 1 x 1000AT/1000AF, 3P, 240V 60Hz, 65KAIC MCCB Compartment 2: Branch Circuit Breakers: 2 x 400AT/600AF 3P, 240V 60Hz, 65KAIC MCCB + 1 x 250AT/600AF 3P, 240V 60Hz, 65KAIC MCCB + 3 space for 600AF, 3P 240V MCCB Compartment 3: 1 x 200AT/250AF 2P, 240V 60Hz 42KAIC MCCB + 2 x 150AT/250AF 2P, 240V 60Hz 42KAIC MCCB + 2 x 100AT/250AF 2P, 240V 60Hz 42KAIC MCCB + 1 space for 250AF 2P, 240V MCCB Complete with accessories, mechanical lugs, grounding bus and digital display metering for Voltage/phase, Current/phase, Frequency/phase in NEMA 3R type enclosure floor mounted	1	395,500.00						
		Supply, Delivery and Installation of Underground Feeder Conductors, Raceways and Transfer Switches								
		CONDUITS, BOXES, FITTINGS & ACCESSORIES								
4	pc	uPVC Pipe thickwall, 32mmØ x 3m	2	132.00						
5	pc	uPVC Pipe thickwall, 40mmØ x 3m	8	267.00						
6	pc	uPVC Pipe thickwall, 50mmØ x 3m	10	367.00						
7	pc	uPVC Pipe thickwall, 65mmØ x 3m	1,924	471.00						
8	pc	uPVC Elbow 32mmØ 90°	2	75.00						
9	pc	uPVC Elbow 40mmØ 90°	4	100.00						
10	pc	uPVC Elbow 50mmØ 90°	6	100.00						
11	pc	uPVC Elbow 65mmØ 45°	48	133.00						
12	pc	uPVC Elbow 65mmØ 90°	91	133.00						
13	set	RSC Clamp 32mmØ w/ screw	6	24.00						
14	set	Conduit Clamp; 40 mm dia, Metal, U-Bolt, Stainless	24	30.00						
15	set	Conduit Clamp; 50 mm dia, Metal, U-Bolt, Stainless	30	38.00						
16	set	Conduit Clamp; 65 mm dia, Metal, U-Bolt, Stainless	20	50.00						
17	length	Z - bar; 1/8"thk. x 1" x 20'	2	1,100.00						
18	set	Expansion shield 1/4"Ø x 2"	30	14.50						
19	pc	Pull Box w/ cover; NEMA 3R 300mm x300mm x150mm Deep	2	700.00						
20	pc	Pull Box w/ cover; NEMA 3R 400mm x400mm x150mm Deep	3	1,000.00						
21	pc	Pull Box w/ cover; NEMA 3R 600mm x600mm x250mm Deep	4	1,200.00						
22	can	PVC Solvent Cement; 400 cc	20	200.00						

1	2	3	4	5	6	7	8	9	10	
Item	Unit of Measure	Brief Description	QTY	ABC/Unit	Unit price EXW per item	Transportation and all other costs incidental to delivery, per item	Sales and other taxes payable if Contract is awarded, per item	Cost of Incidental Services, if applicable, per item	Total Price, per unit (col 5+6+7+8)	Total Price delivered Final Destination (col 9) x (col 4)
23	roll	Caution Buried Electric Line Below Warning Tape 3" x 1000'	3	2,500.00						
		ELECTRICAL WIRINGS, CONNECTORS & ACCESSORIES								
24	meter	Electric wire THWN-2 5.5mm ² Cu. Str., 600V	200	37.00						
25	meter	Electric wire THWN-2 8.0mm ² Cu. Str., 600V	1,723	71.00						
26	meter	Electric wire THWN-2 14mm ² Cu. Str., 600V	1,086	95.00						
27	meter	Electric wire THWN-2 22mm ² Cu. Str., 600V	503.10	197.50						
28	meter	Electric wire THWN-2 30mm ² Cu. Str., 600V	2,158.40	227.00						
29	meter	Electric wire THWN-2 38mm ² Cu. Str., 600V	520	371.00						
30	meter	Electric wire THWN-2 60mm ² Cu. Str., 600V	312	499.00						
31	meter	Electric wire THWN-2 80mm ² Cu. Str., 600V	3,030	594.00						
32	meter	Electric wire THWN-2 100mm ² Cu. Str., 600V	762	747.00						
33	meter	Electric wire THWN-2 125mm ² Cu. Str., 600V	30	1,115.00						
34	meter	Electric wire THWN-2 175mm ² Cu. Stranded, 600V	9,555	1,305.00						
35	pc	Split bolt connector, copper, 60mm ² Stranded	1	500.00						
36	pc	Split bolt connector, copper, 175mm ² Stranded	8	1,300.00						
37	pc	Circuit breaker mechanical lug kit, for 2 x 175mm ² Stranded conductors 400A rated current	6	750.00						
38	pc	Circuit breaker mechanical lug kit, for 2 x 175mm ² Stranded conductors 500A rated current	6	750.00						
39	roll	PVC Tape/19 mm dia x 18 mm	83	30.00						
40	roll	Rubber Tape/ Friction Tape/19 mm dia x 227 g	75	37.00						
		TRANSFER SWITCHES								
41	set	Manual Transfer Switch (MTS) 100AT, 2P, 240V, 60Hz	3	14,300.00						
42	set	Manual Transfer Switch (MTS) 150AT, 2P, 240V, 60Hz	3	19,500.00						
		HANDHOLES & TRENCHES								
43	bags	Portland Cement	168	306.00						
44	cu.m.	Fine Aggregate	32	850.00						
45	cu.m.	Crushed Gravel, 3/4"	18	975.00						
46	pc	10mmØ x 7.5 RSB	27	236.00						
47	pc	10mmØ x 7.5 RSB	53	190.00						
48	kgs	# 16 G.I. Tie Wire	3	75.00						
49	bd.ft.	Coco Form Lumber	96	40.00						
50	pc	1/2" thk. 4' x 8' Marine Plywood	32	610.00						
51	kgs	Assorted Common Nail	3	75.00						
52	lot	INSTALLATION COST	1	3,732,436.42						
		NOTE: LOT EVALUATION								

Name: _____

Legal Capacity: _____

Signature: _____

Duly authorized to sign the Bid for and behalf of: _____

Price Schedule for Goods Offered from Abroad

[shall be submitted with the Bid if bidder is offering goods from Abroad]

For Goods Offered from Abroad

Name of Bidder _____ Project ID No. _____ Page ___ of ___

1	2	3	4	5	6	7	8	9
Item	Description	Country of origin	Quantity	Unit price CIF port of entry (specify port) or CIP named place (specify border point or place of destination)	Total CIF or CIP price per item (col. 4 x 5)	Unit Price Delivered Duty Unpaid (DDU)	Unit price Delivered Duty Paid (DDP)	Total Price delivered DDP (col 4 x 8)

Name: _____

Legal Capacity: _____

Signature: _____

Duly authorized to sign the Bid for and behalf of: _____